



**ADDENDUM NO.3** TO THE CONTRACT DOCUMENTS & Plans

**PROJECT:** *Maintenance Yard Improvements & Sidewalk Extension*

BID NUMBER: 2017-1615

DATE: 10/30/17

YOU ARE HEREBY INSTRUCTED TO READ AND INCORPORATE THIS ADDENDUM  
CONTENTS INTO THE BID SPECIFICATIONS AND CONTRACT DOCUMENTS

1. **Clarify:** Sheet C4 Note 7 Rigid pavement section – The only section of concrete that will be stamped and colored is the hatched area of the concrete entrance off of highway 395, as shown as note 18.
2. **Clarify:** Sheet C10 of the plan set: A soil report was not prepared for the project site and note 1 in the cinder bin detail was not accounted for in the bid documents. Should the soil be that clayey that over excavation is needed the contractor is to notify town staff and we will evaluate the need and area of over excavation and create a change order to cover the cost associated with the work and effort to ensure a suitable base for construction of the wall footing. The CMU block wall will need to span the culvert pipe as indicated in Section A-A of the plan, but the cinder bin was relocated to the front of the site and built into the perimeter wall and is not located at the back of the building over the existing CMP pipe as shown on the detail.
3. Sheet C6 Note 2 remove “8” SDR35 PVC” and replaced with “15 inch RCP Class V”
4. **Add** Base Bid Improvements item 26 showing 15” dia RCP Class V pipe - 25 LF or use the updated bid tab page BF-6a with the item shown as item 20.
5. **Clarify:** BF-6a Base Bid Improvements item 19 “24 DIA RCP add Class III”.
6. **Clarify:** Advertisement for bids AB-3 item 9 (d.) states “Construction contractor’s qualifications statement for engineered Construction, Including Schedules A, B and C” are included in the bid documents as pages BF-3 to BF-5 and BF-8 to BF-10.

Sincerely,

Thomas Dallaire, P.E.  
Gardnerville Town Manager

*Receipt of this Addendum must be acknowledged on the Bid Form.*

**COMPANY NAME:** \_\_\_\_\_

RECEIVED BY: \_\_\_\_\_ DATE: \_\_\_\_\_